# Analysis of Field Control Tests Data for Reliability at S.E.Z Project, Surat, Gujarat

## Desai, Nehal H.

## Desai, M.D.

## Patel, Jaydeep

Research Scholar e-mail: nehal378@hotmail.com Visiting Professor e-mail: earthmdd@yahoo.co.in

M.Tech Student e-mail: jaypatel4114@yahoo.com

AMD, SVNIT, Surat

#### **ABSTRACT**

Mass earthwork covering 50 Hectors area including interior roads for Gems & Jewellery Park developed by Gujarat Hira Bourse was technically scrutinized by Unique Eng. Testing & Advisory Services. The R & D undertaken was planned to adopt core cutter, sand replacement & nuclear density gauge to check the compaction carried out by 12 T vibratory roller. Similarly OMC was checked by Oven drying; Rapid Moisture Meter & nuclear probe. The paper present range of the grading, plasticity & swelling index, proctors modified density CBR for approved borrow area. The technique of construction is explained & control tests have been compared for the reliability. The field variation of moisture & attained density is used to plot filed compaction curve for technique of execution. The paper presents economics, time for control tests & recommends adoption of nuclear gauge both surface & up to 30 cm below for quick economical quality control test & advocate trial run to specify field OMC, MDD for procedure & plants used at site.

**Keywords:** Filed Testing, Monitoring, Earthwork, Quality Control test

## 1. INTRODUCTION

For approx. 50 hectors of land for Gems and Jewellery Park SEZ was selected Near Bhatpore GIDC, Icchapore, Surat. Layout plan is given in Fig. 1. This site was flood prone. Developers Gujarat Hira Bourse planned the lay out as per fig.1. The planning of Roads and plot, to mitigate flood, require sub grade and embankment of 1.5-2.0 m height as shown in typical section in Fig. 2. The sub grade was cohesive moderately expansive soil.




Fig. 1: Layout Plan of SEZ




Fig. 2: Typical Road Section

## **Earthwork**

The site development & road fill required was about 5 lakh m<sup>3</sup> of earthwork under controlled conditions. The client assigned the quality control for the project to

Table 1: Borrow Area Soil

Grai	Grain Size Distribution		LL	PL	PI	FSI in %	MDD in	OMCin	CBR in %
Gravel	Sand	Silt + Clay					gms/cc	%	
0	69	31	22	NP		7	1.884	13.21	20.95
0	70	30	23	NP	-	6	1.824	16.60	13.99
0	70	30	23	NP		12	1.820	14.30	15.00

M/s Unique Engineering Testing Advisory Services. The job required identification of borrow areas, soil characteristics and field daily check of work at site. To optimize the work and ensure accuracy, R & D Techniques were evolved to optimize test time, construction planning and cost of quality control. The contractor adopted 12 T Vibratory roller for the earth compaction. (USBR 1986).

#### **Borrow Area Soil**

Selected borrow pits for required supply of earth were analyzed. The Soil is predominately silty fine sand with variable small fraction of clay. It is non plastic. The range of grain size, index, CBR, OMC & MDD for number of samples is same as per Table 1 permitted only limited checks of physical properties during construction which saves time. (USBR 1986).

## **Quality Control**

The specification of earthwork specified range of moisture is OMC  $\pm$  2 % and dry density 95% MDD as permissible limit. This is expected to ensure stability and CBR for trafficability of roads in industrial complex.

PropertiesR & D programme for data collection and analysis was performed to

- a) Evaluate reliability of nuclear density gauge and rapid moisture meter with respect to conventional oven dry method.
- b) Compare density evaluation with core cutter, sand replacement and nuclear gauge.
- c) Impact of different compacting plant at site (vibratory 12 T roller) on field OMC and field MDD visa vis modified proctor density.

The seasonal temperature and draining properties of sandy soil has impact on loss of moisture at the site.

## 2. ANALYSIS OF DATA OF TESTS

The data of number of test per layer for 20 different road locations have been analyzed. Range of OMC, MDD in field compared to modified proctor is given in Table 2.

The field density attained by Vibratory compaction was higher by 3.4 % with corresponding field moisture less than modified proctor. The field compaction was over by 4 to 6 passes. (Holtz 1952) Average field compaction was 98 % which is higher than specified. The practice considers 24 hrs oven dried test as accurate. The comparison by 3 methods illustrated in Fig 3.

**Table 2:** Range of OMC, MDD in Field Compared to Modified Proctor

Wodined Froctor									
Tested	at Site	Modified Proctor							
MDD in	OMC in %	MDD in	OMC in %						
1.806	12.93	1.741	14.56						
1.814	13.55	-	-						
1.799	13.56	-	-						
	MDD in gms/cc 1.806	in in % gms/cc  1.806 12.93  1.814 13.55	MDD in gms/cc         OMC in gms/cc         MDD in gms/cc           1.806         12.93         1.741           1.814         13.55         -						




Fig. 3: Comparison of Water Content Determined by NDG & RMM w. r. to Oven Drying Method

The test embankments for soil SM-ML were compacted in hot summer with variable moisture to evaluate MDD. The compaction curves for water content by 3 techniques of measurements were developed to assess the impact of roller. The laboratory modified test OMC & MDD are 13.2 % and 1.84 g/cc respectively.

The Rapid moisture quick site test has Min. 1.5 % & Max. 19.9 % error, the range for ND gauge shows Min. 2.74 % & Max. 15.8 %. The error is negative.

Field Moisture Content V/s Dry Density relationship for energy of 12 T Vibratory is shown in Fig. 4.

The site shows moisture variations due to variable temperature from morning to evening (35  $\pm$  7°C) and variable humidity and wind. The field max dry density was highest by core cutter methods and same as lab test by sand replacement.

#### Time to test

Though nuclear gauge requires large capital of Rs. 5 lakhs with calibrations cost of Rs. 15000/- per year, it hardly requires 2 to 3 min. for test. Local core cutter set of Rs. 5000/- requires 15 – 20 min. Similarly sand replacement costing Rs. 10,000/- requires 15 - 20 min.

For moisture content nuclear probe & rapid moisture meter hardly requires 2 min. or less but oven drying takes 24 hrs.



Fig. 4: Photo Plate Showing Testing with NDG

#### 3. CONCLUSIONS

- Selection of borrow pits, its range of soil physical properties compaction characteristics and unsoaked CBR values reduces time to check soil composition specifications.
- The range of variations of OMC MDD modified proctor determines range of accuracy in assessment of compaction at site. For Soil SM-ML for site.
- 3. For Soil SM-ML for site the use of Vibratory roller 12 T 4-6 passes at OMC 1.0 to 2.0 % gave desired compaction for fill and hence CBR. For different roller & environment development of field compaction curve (M/c vs gd) for different Soil will provide guide lines to optimize energy of compaction.

#### ACKNOWLEDGMENTS

Authors are thankful to Applied Mechanics Department of their Institute, Sardar Vallabhbhai National Institute of Technology, Surat and Gujarat Hira Bourse for providing all the facilities and good working environment for research work.

## **REFERENCES:**

Bureau of Reclamation (1986), Laboratory Classification of Soils, *Geotechnical Branch Training Manual No.* 4, 102 pp., Denver Colorado.

Bureau of Reclamation (1986), Soil Classification Handbook, *Geotechnical Branch Training Manual No.* 6, 106 pp., Denver, Colorado.

Holtz, W.G (1952). Notes for Lecture on Compaction and Compaction Specifications (unpublished).

Hunt, Roy E.(1984), Geotechnical Engineering Investigation Manual, Geotechnical Engineering, pp. 47-66, McGraw-Hill Inc.

IS 2720: Part 29, Determination of dry-density of soils in place by core-cutter Method.

Matt Veenstra, David J. White & Vernon R. Schaefer. Rapid Field Testing Techniques for Determining Soil Density and Water Content, Research paper, Department of Civil, Construction and Environmental Engineering, Iowa State University136 Town Engineering Building Ames, IA 50011.

User Manual, Humbolt HS-5001 Nuclear Density Gauge.

Matt Veenstra, David J. White & Vernon R. Schaefer. Rapid Field Testing Techniques for Determining Soil Density and Water Content, Research paper, Department of Civil, Construction and Environmental